



1. Filterra units shipped with top slabs separated from boxes by wooden blocks. Contractor should provide proper lifting equipment. In some cases, lifting hooks may be available.



2. A crane is used with a spreader bar or long slings to unload and set the units. Box is lifted separately from top slab.



3. Filterra boxes are set in pre-prepared holes with appropriate sub-grade per plan elevations.



4. Manufacturer-installed protective throat board and internal silt fabric must be left in place to protect the unit from construction sediment. The top slab is set with butyl tape seal (also supplied).

For more information contact your Filterra representative or Imbrium Systems for assistance at info@imbriumsystems.com or 416-960-9900